



Skiatook Lake, Oklahoma

U.S. ARMY CORPS OF ENGINEERS
FACT SHEET as of February 6, 2012

BUILDING STRONG®

AUTHORIZATION: Flood Control Act of 1962.

TYPE OF PROJECT: Flood damage reduction, recreation, water supply, and environmental stewardship.

PROJECT PHASE: O&M



CONGRESSIONAL INTEREST: Senators Coburn and Inhofe, OK; Representative Lucas, OK-3.

NON-FEDERAL SPONSOR: N/A

BACKGROUND: Skiatook Lake is located at River Mile 14.3 on Hominy Creek, a tributary of Bird Creek in the Verdigris River Basin, about 5 miles west of Skiatook in Osage County, Oklahoma, and about 18 miles northwest of Tulsa in Tulsa County. The dam is a rolled earth-filled embankment 3590 feet long, including the spillway. The uncontrolled spillway is concrete-lined and located in the right abutment. The outlet works includes a gate tower with selective intakes: a 10.5 foot conduit served by two 5x10 foot gates; a 3x5 foot low-flow sluice; and a 36 inch water supply pipe. At conservation pool the lake covers 10,190 acres.

STATUS: FY 2011 activities included routine scheduled operations and maintenance activities at the project. One major maintenance contract was awarded at the project in FY 2011 for repairs to the stilling basin.

ISSUES: Skiatook Lake requires additional funding to provide for critical maintenance that cannot be provided through the regular appropriation. Skiatook Lake requires additional funds to repair the service gates, low flow gates, and liners, and undertake a water reallocation study and associated EIS.

FINANCIAL SUMMARY (\$):

	<u>O&M</u>
Federal Cost Estimate	N/A
Non-Federal Cost Estimate	N/A
Total Project Cost	N/A
Allocation thru FY 2010	N/A
ARRA Funding	\$ 1,196,000
Allocation for FY 2011	\$ 1,465,000
Allocation for FY 2012	\$ 1,732,000
President Budget FY 2013	\$ 2,012,000
Amount That Could Be Used for FY 2013	\$ 4,512,000
Balance to Complete	N/A

SCHEDULE:

FY 2012 Scheduled Work: The current FY 2012 budget will be used for routine operations and maintenance activities at this project.

FY 2013 Budget: The FY 2013 President's budget will be used for routine operations and maintenance activities at this project.

COMPLETION: N/A. Operating project.

For more information regarding the Skiatook Lake project, contact Lake Manager Preston Hunter at (918) 396-3170 or Preston.Hunter@usace.army.mil.

PROJECT MAP SKIATOOK LAKE, OK

